ALLEN TOWNSHIP

NORTHAMPTON COUNTY, PENNSYLVANIA

BID PROPOSALS FOR "JOHN DRIVE RECONSTRUCTION"

ADDENDUM #1 TO BID PACKAGE

JUNE 7, 2016

Form entitled, "MS-944 PAGE 3". Changed to add Approximate Quantities and Units. See attached.

ATTACHMENT 1

pennsylvania DEPARTMENT OF TRANSPORTATION

TO MS - 944 (PROPOSAL AND CONTRACT MS - 944)

County: Northampton Municipality: Allen Township

Project Number:

THIS PORTION TO BE COMPLETED BY THE MUNICIPALITY

LOCATION OF WORK:

John Drive (Between Savage Road and Joseph Drive) - Allen Township, Northampton County, PA

DESCRIPTION OF WORK:
This is a bulk line item bid. Details concerning items below: Superpave Asphalt Mixture Design HMA Base Course, P64-22, 0 to 0.3 ESALS 25 mm 5-1/5" depth; Superpave Asphalt Mixture Design, HMA Binder Course, P64-22, 0 to 0.3 ESALS 19 mm 3" Depth; Superpave Asphalt Mixture Design, HMA Wearing Course 0 to 0.3 ESALS 9.5 mm 2" Depth. Contingency items (#10 through13) listed below are to be installed pursuant the direction of Township's representative.

ESCALATOR CLAUSE:(if adopted by Municipality.)
Bituminous adjustment as per PennDot Publication 408 section 110.04 except see attached resolution. Bituminus price index (IB) will be based on the first advertisment date. Contractor to complete form CS-1PA when bituminous price adjustment is applicable.

SCHEDULE OF PRICES

1 Item No.	2 Approximate Quantities	3 Unit	4 *Description	5 Unit Price	6 Total
1	2,830	SY	Remove Exisitng John Drive (existing paving		
			material) to proposed paving depth (Savage to		
			Joseph). Dispose of material off-site.		
2	2,830	SY	Furnish & Install 6" Depth #4 CABC		
3	2,830	SY	Furnish & Install 6" Depth 2A Modified Stone Ba		
4	2,830	SY	Superpave Asphalt Mixture 25mm 5-1/2 Depth		
5	2,830	SY	Superpave Asphalt Mixture 19mm 3" Depth		
6	2,830	SY	Superpave Asphalt Mixture 9.5mm-2" Depth		
7		Each	Maintenance & Protection Traffic Control		
8		Each	Replace traffic signs		
9		Each	Replace line striping		
10	Contingency	LF	Pavement Base Drain 6"		
11	Contingency	CY	Base Repair/Remove Unsuitable Soils		
12	Contingency	CY	Agregate Replacement of Unsuitable Soils		
13	Contingency	SY	Geotextile Stabilzation		
				SUBTOTAL	

*** DESCRIPTION:**
Must include ADT on wearing surfaces
USE OF CUTBACK ASPHALT IS PROHIBITED BETWEEN MAY 1st AND OCTOBER 31st, EXCEPT AS NOTED IN BULLETIN NO. 25.
FOR OPTION OR PHASE BIDS THE TOTALS FOR EACH MUST BE INCLUDED.

SUBTOTAL FROM OTHER ATTACHMENTS	
BID TOTAL FOR A NON OPTION / PHASE BID	
OPTION 1 OR PHASE 1 BID TOTAL	
OPTION 2 OR PHASE 2 BID TOTAL	
OPTION 3 OR PHASE 3 BID TOTAL	